State of Rhode Island and Providence Plantations Contract Offer

RIVIP BIDDER CERTIFICATION COVER FORM

SECTION 1 - VENDOR INFORMATION

Bid/RFPNumber: 7549007

Bid/RFP Title: ROOF REPAIRS AND MAINTENANCE FOR ALL URI CAMPUSES (40 PGS)

Opening Date & Time: 10/16/2014 11:30 AM

RIVIP Vendor ID #: 72813

Vendor Name: Pawcatuck Roofing Co., Inc.

Address: 20 S. Anguilla Rd.
Box 9B
Pawcatuck , CT 06379
USA

Telephone: 860-599-1024

Fax: 860-599-4250

E-Mail: pawcatuck.roofing@comcast.net

Contact Person: Robert Holland

Title: President

R.I. Foreign Corp #:

NOTICE TO VENDORS

Each bid proposal for a *public works project* must include a "public copy" to be available for public inspection upon the opening of bids. **Bid proposals that do not include a copy for public inspection will be deemed nonresponsive.** For further information on how to comply with this statutory requirement, see R. I. Gen. Laws §§ 37-2-18(b) and (j). Also see Procurement Regulation 5.11, and in addition, for highway and bridge projects, also see Procurement Regulation 5.13, accessible at www.purchasing.ri.gov.

NOTE: AWARD OF CONTRACTS AND PURCHASE ORDERS SHALL BE SUBJECT, AT THE DISCRETION OF THE PURCHASING AGENT, TO THE OFFEROR COMPLETING AN ON-LINE RIVIP REGISTRATION at www.purchasing.ri.gov. It is THE RESPONSIBILITY OF THE VENDOR to make on-line corrections/updates using the Vendor maintenance program on the RI Division of Purchases Web Site.

SECTION 2 – REQUIREMENTS

ALL OFFERS ARE SUBJECT TO THE REQUIREMENTS, PROVISIONS AND PROCEDURES CONTAINED IN THIS CERTIFICATION FORM. Offerors are expected to READ, SIGN and COMPLY WITH all requirements. Failure to do so may be grounds for disqualification of the offer contained herein.

Section 2.1 - RULES FOR SUBMITTING OFFERS

2.1A. This CERTIFICATION FORM MUST BE ATTACHED IN ITS ENTIRETY TO THE FRONT OF THE OFFER and shall be considered an integral part of each offer made by a vendor to enter into a contract with the State of Rhode Island, Division of Purchases. As such, submittal of the entire Bidder Certification Cover Form, signed by a duly authorized representative of the offeror attesting that he/she (1) has read and agrees to comply with the requirements set forth herein and (2) to the accuracy of the information provided and the offer extended, is a mandatory part of any contract award.

To assure that offers are considered on time, each offer must be submitted with the specific Bid/RFP/LOI number (provided above) and the date and time of opening marked in the upper left hand corner of envelope. Each bid/offer must be submitted in separate sealed envelopes.

A complete, signed (in ink) offer package must be delivered to the Division of Purchases (via any mail or messenger service) by the time and date specified for the opening of responses in a sealed envelope.

Bids must be submitted on the RI bid solicitation forms provided, indicating brand and part numbers of items offered, as appropriate. Bidders must submit detailed cuts and specs on items offered as equivalent to brands requested WITH THE OFFER. Bidders must be able to submit samples if requested.
Mail To: Division of Purchases, One Capitol Hill, Second Floor, Providence, RI 02908-5855.

Documents misdirected to other State locations or which are not present in the Division of Purchases at the time of opening for whatever cause will be deemed to be late and will not be considered. For the purposes of this requirement, the official time and date shall be that of the time clock in the Division of Purchases. Postmarks shall not be considered proof of timely submission.

2.1B. RIVIP SOLICITATIONS. To assure maximum access opportunities for users, public bid/RFP solicitations shall be posted on the RIVIP for a minimum of seven days and no amendments shall be made within the last five days before the date an offer is due. Except when access to the Web Site has been severely curtailed and it is determined by the State Purchasing Agent that special circumstances preclude extending a solicitation due date, requests to mail or fax hard copies of solicitations will not be honored. When the result of an Internet solicitation is unsuccessful, the State of Rhode Island will cancel the original solicitation and resolicit the original offer directly from vendors.

2.2. PRICING. Offers are irrevocable for sixty (60) days from the opening date (or such other extended period set forth in the solicitation) and may not be withdrawn, except with the express permission of the State Purchasing Agent. All pricing will be considered to be firm and fixed unless otherwise indicated. The State of Rhode Island is exempt from Federal excise taxes and State Sales and Use Taxes. Such taxes shall not be included in the bid price. PRICES QUOTED ARE FOB DESTINATION.

2.3. DELIVERY and PRODUCT QUALITY. All offers must define delivery dates for all items; if no delivery date is specified, it is assumed that immediate delivery from stock will be made. The contractor will be responsible for delivery of materials in first class condition. Rejected materials will be at vendor's expense.

2.4. PREVAILING WAGE, OSHA SAFETY TRAINING, and APPRENTICESHIP REQUIREMENTS.

Bidders must comply with the provisions of the Rhode Island labor laws, including R. I. Gen. Laws §§ 37-13-1 *et seq.* and occupational safety laws, including R. I. Gen. Laws §§ 28-20-1 *et seq.* These laws mandate for public works construction projects the payment of prevailing wage rates, the implementation and maintenance of occupational safety standards, and for projects with a minimum value of $1 Million, the employment of apprentices. The successful Bidder must submit certifications of compliance with these laws from each of its subcontractors prior to their commencement of any work. Prevailing wage rates, apprenticeship requirements, and other workforce and safety regulations are accessible at www.dlt.ri.gov.

2.5. PUBLIC RECORDS. Offerors are advised that all materials submitted to the State for consideration in response to this solicitation will be considered without exception to be Public Records pursuant to Title 38 Chapter 2 of the Rhode Island General Laws, and will be released for inspection immediately upon request once an award has been made. Offerors are encouraged to attend public bid/RFP openings to obtain information; however, bid/RFP response summaries may be reviewed after award(s) have been made by using the RIVIP at any time or appearing in person at the Division of Purchases Mondays through Fridays between 8:30 a.m. and 3:30 p.m. Telephone requests for results will not be honored. Written requests for results will only be honored if the information is not available on the RIVIP.

SECTION 3 - AWARD DETERMINATION

Award will be made to the responsive and responsible offeror quoting the lowest net price in accordance with specifications, for any individual item(s), for major groupings of items, or for all items listed, at the State's sole option.
3.1. BID SURETY. Where bid surety is required, bidder must furnish a bid bond or certified check for 5% of the bid total with the bid, or for such other amount as may be specified. Bids submitted without a required bid surety will not be considered.

3.2. SPECIFICATIONS. Unless specified "no substitute," product offerings equivalent in quality and performance will be considered (at the sole option of the State) on the condition that the offer is accompanied by detailed product specifications. Offers which fail to include alternate specifications may be deemed nonresponsive.

SECTION 4 – CONTRACT PROVISIONS

4.1. VENDOR AUTHORIZATION TO PROCEED.

4.1A. When a purchase order, change order, contract/agreement or contract/agreement amendment is issued by the RI Division of Purchases, no claim for payment for services rendered or goods delivered contrary to or in excess of the contract terms and scope shall be considered valid unless the vendor has obtained a written change order or contract amendment issued by the Division of Purchases PRIOR TO delivery.

4.1B. Any offer, whether in response to a solicitation for proposals or bids, or made without a solicitation, which is accepted in the form of an order OR Pricing Agreement made in writing by the Purchasing Agent, or a state official with purchasing authority delegated by the Purchasing Agent, shall be considered a binding contract.

4.2. REGULATIONS, GENERAL TERMS AND CONDITIONS GOVERNING STATE CONTRACTS. This solicitation and any contract or purchase order arising from it are issued in accordance with the specific requirements described herein, and the State's Purchasing Laws and Regulations and other applicable State Laws. The Regulations, General Terms and Conditions are incorporated into all state contracts. These regulations and basic information on How To Do Business with the State of Rhode Island are posted on the Rhode Island Vendor Information Program Website (www.purchasing.ri.gov).

4.2A. ARRA SUPPLEMENTAL TERMS AND CONDITIONS. Contracts and sub-awards funded in whole or in part by the American Recovery and Reinvestment Act of 2009. Pub.L.No. 111-5 and any amendments thereto, such contracts and sub-awards, shall be subject to the Supplemental Terms and Conditions For Contracts and Sub-awards Funded in Whole or in Part by the American Recovery and Reinvestment Act of 2009. Pub.L.No. 111-5 and any amendments thereto located on the Division of Purchases website at www.purchasing.ri.gov.

4.3. EQUAL EMPLOYMENT OPPORTUNITY. Compliance certificate and agreement procedures will apply to all awards for supplies or services valued at $10,000 and more. Minority Business Enterprise policies and procedures, including subcontracting opportunities as described in Title 37 Chapter 14.1, of the Rhode Island General Laws, also apply.

4.4. PERFORMANCE BONDS. Where indicated, successful bidder must furnish a 100% performance bond and labor and payment bond for contracts subject to Title 37 Chapters 12 and 13 of the Rhode Island General Laws. All bonds must be furnished by a surety company authorized to conduct business in the State of Rhode Island. Performance bonds must be submitted within 21 calendar days of the issuance of a tentative notice of award.

4.5. DEFAULT and NON-COMPLIANCE. Default and/or non-compliance with the RIVIP requirements and any other aspects of the award may result in withholding of payment(s), contract termination, debarment, suspension, or any other remedy necessary that is in the best interest of the state.

4.6. COMPLIANCE. Vendor must comply with all applicable federal, state and local laws, regulations and ordinances.

4.7. SPRINKLER IMPAIRMENT AND HOT WORK. The Contractor agrees to comply with the practices of the State's insurance carrier for sprinkler impairment and hot work. Prior to performing any work, the Contractor shall obtain the necessary information for compliance from the Risk Management Office at the Department of Administration or the agency for which work will be performed.

SECTION 5 – CERTIFICATIONS AND DISCLOSURES
ALL CONTRACT AWARDS ARE SUBJECT TO THE FOLLOWING DISCLOSURES & CERTIFICATIONS

Offerors must respond to every disclosure statement.
A person authorized to enter into contracts must sign the offer and attest to the accuracy of all statements.

Indicate Yes (Y) or No (N):

N 1. State whether your company, or any owner, stockholder, officer, director, member, partner, or principal thereof, or any subsidiary or affiliated company, has been subject to suspension or debarment by any federal, state, or municipal government agency, or the subject of criminal prosecution, or convicted of a criminal offense within the previous five (5) years. If so, then provide details below.

N 2. State whether your company, or any owner, stockholder, officer, director, member, partner, or principal thereof, or any subsidiary or affiliated company, has had any contracts with a federal, state or municipal government agency terminated for any reason within the previous five (5) years. If so, then provide details below.

N 3. State whether your company or any owner, stockholder, officer, director, member, partner, or principal thereof, or any subsidiary or affiliated company, has been fined more than $5000 for violation(s) of Rhode Island environmental laws by the Rhode Island Department of Environmental Management within the previous five (5) years. If so, then provide details below.

Y 4. I/we certify that I/we will immediately disclose, in writing, to the Chief Purchasing Officer any potential conflict of interest, which may occur during the course of the engagement authorized pursuant to this contract.

Y 5. I/we acknowledge that, in accordance with Chapter 37-2-54(c) of the Rhode Island General Laws "no purchase or contract shall be binding on the state or any agency thereof unless approved by the Department [of Administration] or made under general regulations which the Chief Purchasing Officer may prescribe", including change orders and other types of contracts and under State Purchasing Regulation 8.2.1.1.2, "any alleged oral agreement or arrangements made by a bidder or contractor with any agency or an employee of the Office of Purchases may be disregarded and shall not be binding on the state".

Y 6. I/we certify that I/we or my/our firm possesses all licenses required by Federal and State laws and regulations as they pertain to the requirements of the solicitation and offer made herein and shall maintain such required license(s) during the entire course of the contract resulting from the offer contained herein and should my/our license lapse or be suspended, I/we shall immediately inform the Rhode Island State Purchasing Agent in writing of such circumstance.

Y 7. I/we certify that I/we will maintain required insurance during the entire course of the contract resulting from the offer contained herein and should my/our insurance lapse or be suspended, I/we shall immediately inform the Rhode Island State Purchasing Agent in writing of such circumstance.

Y 8. I/we certify that I/we understand that falsification of any information herein or failure to notify the Rhode Island State Purchasing Agent as certified herein may be grounds for suspension, debarment and/or prosecution for fraud.

Y 9. I/we acknowledge that the provisions and procedures set forth in this form apply to any contract arising from this offer.

Y 10. I/we acknowledge that I/we understand the State's Purchasing Laws (37-2 of the General Laws of Rhode Island) and Purchasing Regulations and General Terms and Conditions available at the Rhode Island Division of Purchases Website (www.purchasing.ri.gov) apply as the governing conditions for any contract or purchase order I/we may receive from the State of Rhode Island, including the offer contained herein.

Y 11. I/We certify that the bidder: (i) is not identified on the General Treasurer's list, created pursuant to R.I. Gen. Laws § 37-2.5-3, as a person or entity engaging in investment activities in Iran described in § 37-2.5-2(b); and (ii) is not engaging in any such investment activities in Iran.

Y 12. I/we certify that the above vendor information is correct and complete.

IF YOU HAVE ANSWERED "YES" TO QUESTIONS #1–3 OR IF YOU ARE UNABLE TO CERTIFY YES TO ITEMS #4–12 OF THE FOREGOING, PROVIDE DETAILS/EXPLANATION BELOW AND/OR IN AN ATTACHED STATEMENT. INCOMPLETE CERTIFICATION FORMS SHALL BE GROUNDS FOR DISQUALIFICATION OF OFFER.

Signature below commits vendor to the attached offer and certifies (1) that the offer has taken into account all solicitation amendments, (2) that the above statements and information are accurate and that vendor understands and has complied with the requirements set forth herein. When delivering offers in person to One Capitol Hill, vendors are advised to allow at least one hour additional time for clearance through security checkpoints.

Date 10/15/14

Vendor's Signature (Person authorized to enter into contracts; signature must be in ink.)

Robert J. Holland, President

Print Name and Title of company official signing offer

Request for Quote

STATE OF RHODE ISLAND AND PROVIDENCE PLANTATIONS
ONE CAPITOL HILL
PROVIDENCE RI 02908

CREATION DATE : 12-SEP-14
BID NUMBER: 7549007
TITLE: Roofing Repairs and Maintenance for ALL URI Campuses, URI

BLANKET START : 01-NOV-14
BLANKET END : 31-DEC-17
BID CLOSING DATE AND TIME:16-OCT-2014 11:30:00

BUYER: Ohara 2nd, John F
PHONE #: 401-574-8125

BILL TO
URI ACCOUNTS PAYABLE
CARLOTTI ADMINISTRATION BLDG
75 LOWER COLLEGE ROAD, SUITE 1
KINGSTON, RI 02881
US

SHIP TO
URI FACILITIES RECEIVING
ATTN: SEE BELOW
SHERMAN BLDG
KINGSTON, RI 02881
US

Requistion Number: 1364675

Line	Description	Quantity	Unit	Unit Price	Total
	Blanket Requirement: November 1, 2014 - December 31, 2017. A Zip File is attached that included an Excel Spreadsheet for submission of vendor quotes for each of the years. Attachment "A" is a sample ONLY of the bidding spreadsheet. DUE TO LENGTH OF BID AND TIME CONSTRAINTS, THE STATE WILL ONLY ACKNOWLEDGE RECEIPT AND READ THE NAMES OF VENDORS SUBMITTING PROPOSALS. NO EXAMINATION OF DOCUMENTS OR PRESENTATION OF INFORMATION CONTAINED IN PROPOSALS WILL BE MADE AVAILABLE AT THE BID OPENING; HOWEVER, INSTRUCTIONS TO OBTAIN THE TABULATION OR SUMMARY OF BID RESPONSES WILL BE MADE AVAILABLE AT THE RI DIVISION OF PURCHASES WEBSITE AT WWW.PURCHASING.RI.GOV				
1	11/1/2014 - 12/31/2017 Roofing repairs and maintenance for all University of RI campuses per the attached specifications.	1.00	Total	Line Items $23,856.00	$865,947.00

Delivery: _____

Terms of Payment: _____

It is the Vendor's responsibility to check and download any and all addenda from the RIVIP. This offer may not be considered unless a signed RIVIP generated Bidder Certification Cover Form is attached and the Unit Price column is completed. The signed Certification Cover Form must be attached to the front of the offer

ATTACHMENT "A" - SOLICITATION PRICING SHEET

LINE	Solicitation #7549007	ESTIMATED QUANTITY	MEASURE OF UNIT	PRICE PER MEASURE UNIT
*	Provide all line items with a unit price and a total cost. Leaving any item unaddressed may invalidate bid.	*****	*****	*****
*	>>>>>>>>Prices for the Period of 11-1-2014 - 6-30-2015<<<<<<<<	*****	*****	*****
*	Remove existing, provide & install new EPDM (rubber) membrane	*****	*****	*****
1	a) Fully Adhered	500	sq. ft.	$6.00
2	b) Ballasted	500	sq. ft.	$6.50
3	c) Mechanically Fastened	500	sq. ft.	$6.00
*	Repair seams or replace damaged EPDM including all necessary prep work.	*****	*****	*****
4	a) Fully Adhered	250	lf.	$10.00
5	b) Ballasted	250	lf.	$15.00
6	c) Mechanically Fastened	250	lf.	$10.00
*	Prepare existing surface and provide & install Modified Bitumen membrane.	*****	*****	*****
7	a) 4mm APP to smooth surface	500	sq. ft.	$4.00
8	b) 4mm APP to gravel surface	500	sq. ft.	$5.00
9	c) 4mm SBS to smooth surface	500	sq. ft.	$5.00
10	d) 4mm SBS to gravel surface	500	sq. ft.	$6.50
*	Remove existing, provide & install single ply membrane of:	*****	*****	*****
11	a) PVC	500	sq. ft.	$6.00
12	b) CPE	500	sq. ft.	$6.00
13	c) Tripolimer	500	sq. ft.	$6.00
14	Remove existing, provide & install built up 4 ply fiberglass type IV roofing felts in hot Perma mop roofing asphalt	500	sq. ft.	$12.00
15	Provide & install 5 courses of plastic cement and webbing overlayment.	10	sq. ft.	$10.00
*	Provide & install overlayment of 60 lbs. floodcoat of Perma Mop roofing asphalt with 400 lbs. gravel 3/8, 5/8 inch size at a uniform rate. (per 100 sq. ft.)	*****	*****	*****
16	a) Smooth surface	500	sq. ft.	$12.50
17	b) Graveled surface	1,000	sq. ft.	$15.00
18	Patch joints in corrugated metal roofing.	100	lf.	$10.00
19	Blister repair (area encompassing blister) 1-ft. extension cuts.	50	sq. ft.	$3.00
20	Provide & install asphalt emulsion non-fiberated roof coating.	250	sq. ft.	$3.50
21	Provide & install aluminum non-fiberated roof coating.	1	gal.	$2.00
22	Remove existing rolled roofing, provide & install mineral- surfaced rolled roofing over exposed roof deck.	100	sq. ft.	$2.50
23	Provide & install uncured EPDM 12" wide strip for seam resealent	100	lf.	$15.00
24	Provide & install, peel & stick nominal 25 mil cured butyl tape	100	lf.	$10.00
25	Provide & install non-fiberated flashing cement.	1	gal.	$25.00
26	Provide & install tar roof re-saturant	1	gal.	$25.00
27	Provide & install a #28 fiberglass base sheet in a full mopping of hot Perma Mop roofing asphalt as a vapor barrier	500	sq. ft.	$10.00
*	Provide & install polyisocyanurate asphalt faced roofing insulation			
28	a) 1 inch thickness	500	sq. ft.	$1.50
29	b) 2 inch thickness	500	sq. ft.	$2.00
30	c) 3 inch thickness	500	sq. ft.	$2.50
*	Provide & install tapered polyisocyanurate asphalt faced	*****	*****	*****
31	a) 1/8" per ft.taper	500	sq. ft.	$3.00
32	b) 1/4" per ft.taper	500	sq. ft.	$4.00
33	Provide & install Tapered fiberboard 1/8" per ft. taper	500	sq. ft.	$3.50
34	Provide & install 1/2 inch fiberboard (High Density)	500	sq. ft.	$4.50
*	Remove existing, provide & install Wood nailers (pressure treated)	*****	*****	*****
35	a) 2"x 6"	100	bf.	$5.00
36	b) 2"x 8"	100	bf.	$6.00
*	Remove existing, provide & install plywood sheathing	*****	*****	*****
37	a) 1/2"	32	sq. ft.	$0.60
38	b) 3/4"	32	sq. ft.	$0.75
39	c) 1"	32	sq. ft.	$1.00
*	Remove existing, provide & install t&g	*****	*****	*****
40	a) 1"x 4"	100	bf.	$1.00
41	b) 1"x 6"	100	bf.	$1.20
42	c) 1"x 8"	100	bf.	$1.50
43	d) 2"x 4"	50	bf.	$5.00
44	e) 2"x 6"	50	bf.	$6.00
*	Remove existing, provide & install trim & fascia board.	*****	*****	*****
45	a) 1"x 4"	25	bf.	$1.00
46	b) 1"x 6"	50	bf.	$1.25
47	c) 1"x 8"	50	bf.	$1.50
48	d) 2"x 6"	25	bf.	$2.00
49	e) 2"x 8"	25	bf.	$5.00
50	Provide & install 4" x 4" lumber (pressure treated)	50	bf.	$6.00
*	Repair or replace rafter tails (pressure treated)	*****	*****	*****
51	a) 2" x 4"	50	bf.	$5.00
52	b) 2" x 6"	50	bf.	$6.00
53	c) 2" x 8"	50	bf.	$8.00
*	Remove existing shingles and replace over exposed roof deck 15 lb. felt with 40 year limited warranty Fiberglass asphalt shingles.	*****	*****	*****
54	a) (3 tab) (ASTM-ANSI D-312) minimum weight 320 lbs. per sq.	1,000	sq. ft.	$3.95
*	Provide & install 30 year limited warranty Fiberglas asphalt shingles over existing roof covering.	*****	*****	*****
55	a) (3 Tab) (ASTM-ANSI D-312) Minimum weight 265 lbs. per sq.	1,000	sq. ft.	$3.50
56	Provide & install ridge vents 18 sq. inches free air per lineal ft.	50	lf.	$3.30
*	Provide & install soffit vents 9 sq. inches free air per lineal ft.	*****	*****	*****
57	a) one story building	50	lf.	$5.00
58	b) two story building	50	lf.	$7.00
59	c) three story building	50	lf.	$10.00
60	d) four story building	50	lf.	$15.50

ATTACHMENT "A" - SOLICITATION PRICING SHEET

LINE	Solicitation #7549007	ESTIMATED QUANTITY	MEASURE OF UNIT	PRICE PER MEASURE UNIT
*	Provide all line items with a unit price and a total cost. Leaving any item unaddressed may invalidate bid.	*****	*****	*****
*	>>>>>>>>Prices for the Period of 11-1-2014 - 6-30-2015<<<<<<<<	*****	*****	*****
*	Provide & Install replacement roofing slates with 90 lbs. Polyester reinforced felt underlayment to match existing in color, thickness, texture, size. install with copper nails.	*****	*****	*****
61	a) 4 inch width	50	lf.	$35.00
62	b) 6 inch width	50	lf.	$45.00
63	c) 8 inch width	50	lf.	$55.00
64	d) 10 inch width	50	lf.	$65.00
65	e) 12 inch width	50	lf.	$65.00
66	Provide & Install Imitation slate install ceramic slate; 580 lbs. Per square; 60 year limited warranty. 10 7/8 inches X 16 inches with 90 lbs. Polyester reinforced felt underlayment. Install with stainless steel fasteners.	50	sq. ft.	$12.75
67	Provide & install reglets 5" max. s.o.	50	lf.	$5.00
68	Repair reglets	50	lf.	$5.00
69	Rake joints & cracks	100	lf.	$5.00
*	Restore pitch pockets	*****	*****	*****
70	a) Copper	1	ea.	$75.00
71	b) Aluminum	1	ea.	$75.00
*	Seal gutter joints	*****	*****	*****
72	a) Solder copper	50	lf.	$6.50
73	b) Liquid for aluminum	50	lf.	$75.00
74	Provide & install urethane sealant caulking	100	lf.	$5.00
*	Provide & install Fascia metal trim. 6 inch width.	*****	*****	*****
75	a) Aluminum .032 gage	100	lf.	$3.50
76	b) Aluminum .040 gage	100	lf.	$4.50
77	c) Copper lead coated 16 oz.	100	lf.	$15.00
78	d) Copper uncoated 16 oz.	100	lf.	$12.50
*	Provide & install 5"x5" gutters and corrugated downspouts	*****	*****	*****
79	a) Copper uncoated	100	lf.	$55.00
80	b) Copper lead coated	100	lf.	$75.00
81	c) Aluminum seamless .032 gage	100	lf.	$10.00
82	d) Aluminum seamless .040 gage	100	lf.	$15.00
*	Provide & install counterflashing	*****	*****	*****
83	a) Copper uncoated	25	lf.	$10.00
84	b) Copper lead coated	50	sq. ft.	$15.00
85	c) Aluminum .032 gage	50	sq. ft.	$5.00
86	d) Aluminum .040 gage	25	sq. ft.	$6.00
*	Provide & install vent flashing	*****	*****	*****
87	a) Copper 16 oz.	20	sq. ft.	$2.50
88	b) Copper 20 oz.	20	sq. ft.	$3.00
89	c) Lead coated copper 16 oz.	20	sq. ft.	$3.50
90	d) Lead coated copper 20 oz.	20	sq. ft.	$4.00
*	Provide & install gravel stops and drip edges	*****	*****	*****
91	a) Copper uncoated 16 oz.	100	lf.	$15.00
92	b) Copper uncoated 20 oz.	100	lf.	$20.00
93	c) Copper lead coated 16 oz.	100	lf.	$25.00
94	d) Aluminum .032 gage	100	lf.	$10.00
95	e) Aluminum .040 gage	100	lf.	$12.00
96	Provide and install reglets 6" max S.O.	15	lf.	$10.00
97	Provide and install unreinforced peel and stick ice and water barrier	100	sq. ft.	$0.60
98	Provide all materials & labor necessary for test cuts to roof to ascertain the extent of damage.	1	cut	$225.00
99	Provide lab tests for asbestos for test cut of suspect roofing materials.	100	each test	$250.00
100	Provide hourly rates for estimators to do site visits and provide cost estimates for requested work.	50	Hours	$95.00
101	Journeyman roofer overtime rate per hour	100	Hours	$135.00
102	Carpenter overtime rate per hour	100	Hours	$100.00
*	Seal gutter joints	*****	*****	*****
103	a) solder copper	25	lf.	$50.00
104	b) liquid for aluminum	25	lf.	$15.00
*	Provide &Install Securock	*****	*****	*****
105	a) 3/8"	320	sq. ft.	$0.65
106	b) 1/2"	320	sq. ft.	$0.75
107	Provide 65' crane	1	per hour	$125.00
108	Provide 65' crane	1	per 1/2 day	$800.00
109	Provide 65' crane	1	per day	$1,500.00
110	Provide and install styrene based liquid applied roofing. (similar to Kemper).	500	sq. ft.	$7.00
*	Provide and install CHEM CURB liquid applied Pitch pockets	*****	*****	*****
111	a) 4 1/2" I.D.	1	ea	$550.00
112	b) 7 1/2" I.D'	1	ea	$650.00
113	Discount off list for materials not listed.	Percent		%

ATTACHMENT "A" - SOLICITATION PRICING SHEET

LINE	Solicitation #7549007	ESTIMATED QUANTITY	MEASURE OF UNIT	PRICE PER MEASURE UNIT
*	**Provide all line items with a unit price and a total cost. Leaving any item unaddressed may invalidate bid.**	*****	*****	*****
*	**>>>>>>>>Prices for the Period of 7-1-2015 - 6-30-2016<<<<<<<<**	*****	*****	*****
*	Remove existing, provide & install new EPDM (rubber) membrane	*****	*****	*****
114	a) Fully Adhered	500	sq. ft.	$6.15
115	b) Ballasted	500	sq. ft.	$6.66
116	c) Mechanically Fastened	500	sq. ft.	$6.15
*	Repair seams or replace damaged EPDM including all necessary prep work.	*****	*****	
117	a) Fully Adhered	250	lf.	$10.25
118	b) Ballasted	250	lf.	$15.38
119	c) Mechanically Fastened	250	lf.	$10.25
*	Prepare existing surface and provide & install Modified Bitumen membrane.	*****	*****	*****
120	a) 4mm APP to smooth surface	500	sq. ft.	$4.10
121	b) 4mm APP to gravel surface	500	sq. ft.	$5.13
122	c) 4mm SBS to smooth surface	500	sq. ft.	$5.13
123	d) 4mm SBS to gravel surface	500	sq. ft.	$6.66
*	Remove existing, provide & install single ply membrane of:	*****	*****	*****
124	a) PVC	500	sq. ft.	$6.15
125	b) CPE	500	sq. ft.	$6.15
126	c) Tripolimer	500	sq. ft.	$6.15
127	Remove existing, provide & install built up 4 ply fiberglass type IV roofing felts in hot Perma mop roofing asphalt	500	sq. ft.	$12.30
128	Provide & install 5 courses of plastic cement and webbing overlayment.	10	sq. ft.	$10.25
*	Provide & install overlayment of 60 lbs. floodcoat of Perma Mop roofing asphalt with 400 lbs. gravel 3/8, 5/8 inch size at a uniform rate. (per 100 sq. ft.)	*****	*****	*****
129	a) Smooth surface	500	sq. ft.	$12.81
130	b) Graveled surface	1,000	sq. ft.	$15.38
131	Patch joints in corrugated metal roofing.	100	lf.	$10.25
132	Blister repair (area encompassing blister) 1-ft. extension cuts.	50	sq. ft.	$3.08
133	Provide & install asphalt emulsion non-fiberated roof coating.	250	sq. ft.	$3.59
134	Provide & install aluminum non-fiberated roof coating.	1	gal.	$2.05
135	Remove existing rolled roofing, provide & install mineral- surfaced rolled roofing over exposed roof deck.	100	sq. ft.	$2.56
136	Provide & install uncured EPDM 12" wide strip for seam resealent	100	lf.	$15.38
137	Provide & install, peel & stick nominal 25 mil cured butyl tape	100	lf.	$10.25
138	Provide & install non-fiberated flashing cement.	1	gal.	$25.63
139	Provide & install tar roof re-saturant	1	gal.	$25.63
140	Provide & install a #28 fiberglass base sheet in a full mopping of hot Perma Mop roofing asphalt as a vapor barrier	500	sq. ft.	$10.25
*	Provide & install polyisocyanurate asphalt faced roofing insulation	*****	*****	*****
141	a) 1 inch thickness	500	sq. ft.	$1.54
142	b) 2 inch thickness	500	sq. ft.	$2.05
143	c) 3 inch thickness	500	sq. ft.	$2.56
*	Provide & install tapered polyisocyanurate asphalt faced	*****	*****	*****
144	a) 1/8" per ft.taper	500	sq. ft.	$3.08
145	b) 1/4" per ft.taper	500	sq. ft.	$4.10
146	Provide & install Tapered fiberboard 1/8" per ft. taper	500	sq. ft.	$3.59
147	Provide & install 1/2 inch fiberboard (High Density)	500	sq. ft.	$4.61
*	Remove existing, provide & install Wood nailers (pressure treated)	*****	*****	*****
148	a) 2"x 6"	100	bf.	$5.13
149	b) 2"x 8"	100	bf.	$6.15
*	Remove existing, provide & install plywood sheathing	*****	*****	*****
150	a) 1/2"	32	sq. ft.	$0.62
151	b) 3/4"	32	sq. ft.	$0.77
152	c) 1"	32	sq. ft.	$1.03
*	Remove existing, provide & install t&g	*****	*****	*****
153	a) 1"x 4"	100	bf.	$1.03
154	b) 1"x 6"	100	bf.	$1.23
155	c) 1"x 8"	100	bf.	$1.54
156	d) 2"x 4"	50	bf.	$5.13
157	e) 2"x 6"	50	bf.	$6.15
*	Remove existing, provide & install trim & fascia board.	*****	*****	*****
158	a) 1"x 4"	25	bf.	$1.03
159	b) 1"x 6"	50	bf.	$1.28
160	c) 1"x 8"	50	bf.	$1.54
161	d) 2"x 6"	25	bf.	$2.05
162	e) 2"x 8"	25	bf.	$5.13
163	Provide & install 4" x 4" lumber (pressure treated)	50	bf.	$6.15
*	Repair or replace rafter tails (pressure treated)	*****	*****	*****
164	a) 2" x 4"	50	bf.	$5.13
165	b) 2" x 6"	50	bf.	$6.15
166	c) 2" x 8"	50	bf.	$8.20
*	Remove existing shingles and replace over exposed roof deck 15 lb. felt with 40 year limited warranty Fiberglass asphalt shingles.	*****	*****	*****
167	a) (3 tab) (ASTM-ANSI D-312) minimum weight 320 lbs. per sq.	1,000	sq. ft.	$4.05
*	Provide & install 30 year limited warranty Fiberglas asphalt shingles over existing roof covering.	*****	*****	*****
168	a) (3 Tab) (ASTM-ANSI D-312) Minimum weight 265 lbs. per sq.	1,000	sq. ft.	$3.59
169	Provide & install ridge vents 18 sq. inches free air per lineal ft.	50	lf.	$3.38
*	Provide & install soffit vents 9 sq. inches free air per lineal ft.	*****	*****	*****
170	a) one story building	50	lf.	$5.13
171	b) two story building	50	lf.	$7.18
172	c) three story building	50	lf.	$10.25
173	d) four story building	50	lf.	$15.89

ATTACHMENT "A" - SOLICITATION PRICING SHEET

LINE	Solicitation #7549007	ESTIMATED QUANTITY	MEASURE OF UNIT	PRICE PER MEASURE UNIT
*	**Provide all line items with a unit price and a total cost. Leaving any item unaddressed may invalidate bid.**	*****	*****	*****
*	**>>>>>>>>Prices for the Period of 7-1-2015 - 6-30-2016<<<<<<<<**	*****	*****	*****
*	Provide & Install replacement roofing slates with 90 lbs. Polyester reinforced felt underlayment to match existing in color, thickness, texture, size. install with copper nails.	*****	*****	*****
174	a) 4 inch width	50	lf.	$35.88
175	b) 6 inch width	50	lf.	$46.13
176	c) 8 inch width	50	lf.	$56.38
177	d) 10 inch width	50	lf.	$66.63
178	e) 12 inch width	50	lf.	$66.63
179	Provide & Install Imitation slate install ceramic slate; 580 lbs. Per square; 60 year limited warranty. 10 7/8 inches X 16 inches with 90 lbs. Polyester reinforced felt underlayment. Install with stainless steel fasteners.	50	sq. ft.	$13.07
180	Provide & install reglets 5" max. s.o.	50	lf.	$5.13
181	Repair reglets	50	lf.	$5.13
182	Rake joints & cracks	100	lf.	$5.13
*	Restore pitch pockets	*****	*****	*****
183	a) Copper	1	ea.	$76.88
184	b) Aluminum	1	ea.	$76.88
*	Seal gutter joints	*****	*****	*****
185	a) Solder copper	50	lf.	$6.66
186	b) Liquid for aluminum	50	lf.	$76.88
187	Provide & install urethane sealant caulking	100	lf.	$5.13
*	Provide & install Fascia metal trim. 6 inch width.	*****	*****	*****
188	a) Aluminum .032 gage	100	lf.	$3.59
189	b) Aluminum .040 gage	100	lf.	$4.61
190	c) Copper lead coated 16 oz.	100	lf.	$15.38
191	d) Copper uncoated 16 oz.	100	lf.	$12.81
*	Provide & install 5"x5" gutters and corrugated downspouts	*****	*****	*****
192	a) Copper uncoated	100	lf.	$56.38
193	b) Copper lead coated	100	lf.	$76.88
194	c) Aluminum seamless .032 gage	100	lf.	$10.25
195	d) Aluminum seamless .040 gage	100	lf.	$15.38
*	Provide & install counterflashing	*****	*****	*****
196	a) Copper uncoated	25	lf.	$10.25
197	b) Copper lead coated	50	sq. ft.	$15.38
198	c) Aluminum .032 gage	50	sq. ft.	$5.13
199	d) Aluminum .040 gage	25	sq. ft.	$6.15
*	Provide & install vent flashing	*****	*****	*****
200	a) Copper 16 oz.	20	sq. ft.	$2.56
201	b) Copper 20 oz.	20	sq. ft.	$3.08
202	c) Lead coated copper 16 oz.	20	sq. ft.	$3.59
203	d) Lead coated copper 20 oz.	20	sq. ft.	$4.10
*	Provide & install gravel stops and drip edges	*****	*****	*****
204	a) Copper uncoated 16 oz.	100	lf.	$15.38
205	b) Copper uncoated 20 oz.	100	lf.	$20.50
206	c) Copper lead coated 16 oz.	100	lf.	$25.63
207	d) Aluminum .032 gage	100	lf.	$10.25
208	e) Aluminum .040 gage	100	lf.	$12.30
209	Provide and install reglets 6" max S.O.	15	lf.	$10.25
210	Provide and install unreinforced peel and stick ice and water barrier	100	sq. ft.	$0.62
211	Provide all materials & labor necessary for test cuts to roof to ascertain the extent of damage.	1	cut	$230.63
212	Provide lab tests for asbestos for test cut of suspect roofing materials.	100	each test	$256.25
213	Provide hourly rates for estimators to do site visits and provide cost estimates for requested work.	50	Hours	$97.38
214	Journeyman roofer overtime rate per hour	100	Hours	$138.38
215	Carpenter overtime rate per hour	100	Hours	$102.50
*	Seal gutter joints	*****	*****	*****
216	a) solder copper	25	lf.	$51.25
217	b) liquid for aluminum	25	lf.	$15.38
*	Provide &Install Securock	*****	*****	*****
218	a) 3/8"	320	sq. ft.	$0.67
219	b) 1/2"	320	sq. ft.	$0.77
220	Provide 65' crane	1	per hour	$128.13
221	Provide 65' crane	1	per 1/2 day	$820.00
222	Provide 65' crane	1	per day	$1,537.50
223	Provide and install styrene based liquid applied roofing. (similar to Kemper).	500	sq. ft.	$7.18
*	Provide and install CHEM CURB liquid applied Pitch pockets	*****	*****	*****
224	a) 4 1/2" I.D.	1	ea	$563.75
225	b) 7 1/2" I.D'	1	ea	$666.25
226	Discount off list for materials not listed.	Percent		%
*	Remove existing, provide & install new EPDM (rubber) membrane	*****	*****	*****
227	a) Fully Adhered	500	sq. ft.	$6.30
228	b) Ballasted	500	sq. ft.	$6.83
229	c) Mechanically Fastened	500	sq. ft.	$6.30
*	Repair seams or replace damaged EPDM including all necessary prep work.	*****	*****	*****
230	a) Fully Adhered	250	lf.	$10.51
*	**Provide all line items with a unit price and a total cost. Leaving any item unaddressed may invalidate bid.**	*****	*****	*****

ATTACHMENT "A" - SOLICITATION PRICING SHEET

LINE	Solicitation #7549007	ESTIMATED QUANTITY	MEASURE OF UNIT	PRICE PER MEASURE UNIT
*	>>>>>>>>Prices for the Period of 7-1-2016 - 6-30-2017<<<<<<<<	*****	*****	*****
231	b) Ballasted	250	lf.	$15.76
232	c) Mechanically Fastened	250	lf.	$10.51
*	Prepare existing surface and provide & install Modified Bitumen membrane.	*****	*****	*****
233	a) 4mm APP to smooth surface	500	sq. ft.	$4.20
234	b) 4mm APP to gravel surface	500	sq. ft.	$5.25
235	c) 4mm SBS to smooth surface	500	sq. ft.	$5.25
236	d) 4mm SBS to gravel surface	500	sq. ft.	$6.83
*	Remove existing, provide & install single ply membrane of:	*****	*****	*****
237	a) PVC	500	sq. ft.	$6.30
238	b) CPE	500	sq. ft.	$6.30
239	c) Tripolimer	500	sq. ft.	$6.30
240	Remove existing, provide & install built up 4 ply fiberglass type IV roofing felts in hot Perma mop roofing asphalt	500	sq. ft.	$12.61
241	Provide & install 5 courses of plastic cement and webbing overlayment.	10	sq. ft.	$10.51
*	Provide & install overlayment of 60 lbs. floodcoat of Perma Mop roofing asphalt with 400 lbs. gravel 3/8, 5/8 inch size at a uniform rate. (per 100 sq. ft.)	*****	*****	*****
242	a) Smooth surface	500	sq. ft.	$13.13
243	b) Graveled surface	1,000	sq. ft.	$15.76
244	Patch joints in corrugated metal roofing.	100	lf.	$10.51
245	Blister repair (area encompassing blister) 1-ft. extension cuts.	50	sq. ft.	$3.15
246	Provide & install asphalt emulsion non-fiberated roof coating.	250	sq. ft.	$3.68
247	Provide & install aluminum non-fiberated roof coating.	1	gal.	$2.10
248	Remove existing rolled roofing, provide & install mineral- surfaced rolled roofing over exposed roof deck.	100	sq. ft.	$2.63
249	Provide & install uncured EPDM 12" wide strip for seam resealent	100	lf.	$15.76
250	Provide & install, peel & stick nominal 25 mil cured butyl tape	100	lf.	$10.51
251	Provide & install non-fiberated flashing cement.	1	gal.	$26.27
252	Provide & install tar roof re-saturant	1	gal.	$26.27
253	Provide & install a #28 fiberglass base sheet in a full mopping of hot Perma Mop roofing asphalt as a vapor barrier	500	sq. ft.	$10.51
*	Provide & install polyisocyanurate asphalt faced roofing insulation	*****	*****	*****
254	a) 1 inch thickness	500	sq. ft.	$1.58
255	b) 2 inch thickness	500	sq. ft.	$2.10
256	c) 3 inch thickness	500	sq. ft.	$2.62
*	Provide & install tapered polyisocyanurate asphalt faced	*****	*****	*****
257	a) 1/8" per ft.taper	500	sq. ft.	$3.15
258	b) 1/4" per ft.taper	500	sq. ft.	$4.20
259	Provide & install Tapered fiberboard 1/8" per ft. taper	500	sq. ft.	$3.68
260	Provide & install 1/2 inch fiberboard (High Density)	500	sq. ft.	$4.73
*	Remove existing, provide & install Wood nailers (pressure treated)	*****	*****	*****
261	a) 2"x 6"	100	bf.	$5.25
262	b) 2"x 8"	100	bf.	$6.30
*	Remove existing, provide & install plywood sheathing	*****	*****	*****
263	a) 1/2"	32	sq. ft.	$0.63
264	b) 3/4"	32	sq. ft.	$0.79
265	c) 1"	32	sq. ft.	$1.05
*	Remove existing, provide & install t&g	*****	*****	*****
266	a) 1"x 4"	100	bf.	$1.05
267	b) 1"x 6"	100	bf.	$1.26
268	c) 1"x 8"	100	bf.	$1.58
269	d) 2"x 4"	50	bf.	$5.25
270	e) 2"x 6"	50	bf.	$6.30
*	Remove existing, provide & install trim & fascia board.	*****	*****	*****
271	a) 1"x 4"	25	bf.	$1.05
272	b) 1"x 6"	50	bf.	$1.31
273	c) 1"x 8"	50	bf.	$1.58
274	d) 2"x 6"	25	bf.	$2.10
275	e) 2"x 8"	25	bf.	$5.25
276	Provide & install 4" x 4" lumber (pressure treated)	50	bf.	$6.30
*	Repair or replace rafter tails (pressure treated)	*****	*****	*****
277	a) 2" x 4"	50	bf.	$5.25
278	b) 2" x 6"	50	bf.	$6.30
279	c) 2" x 8"	50	bf.	$8.41
*	Remove existing shingles and replace over exposed roof deck 15 lb. felt with 40 year limited warranty Fiberglass asphalt shingles.	*****	*****	*****
280	a) (3 tab) (ASTM-ANSI D-312) minimum weight 320 lbs. per sq.	1,000	sq. ft.	$3.68
*	Provide & install 30 year limited warranty Fiberglas asphalt shingles over existing roof covering.	*****	*****	*****
281	a) (3 Tab) (ASTM-ANSI D-312) Minimum weight 265 lbs. per sq.	1,000	sq. ft.	$3.68
282	Provide & install ridge vents 18 sq. inches free air per lineal ft.	50	lf.	$3.47
*	Provide & install soffit vents 9 sq. inches free air per lineal ft.	*****	*****	*****
283	a) one story building	50	lf.	$5.25
284	b) two story building	50	lf.	$7.35
285	c) three story building	50	lf.	$10.51
286	d) four story building	50	lf.	$16.28
*	Provide & Install replacement roofing slates with 90 lbs. Polyester reinforced felt underlayment to match existing in color, thickness, texture, size. install with copper nails.	*****	*****	*****
287	a) 4 inch width	50	lf.	$36.77
288	b) 6 inch width	50	lf.	$47.28
289	c) 8 inch width	50	lf.	$57.78
290	d) 10 inch width	50	lf.	$68.29
291	e) 12 inch width	50	lf.	$68.29

ATTACHMENT "A" - SOLICITATION PRICING SHEET

LINE	Solicitation #7549007	ESTIMATED QUANTITY	MEASURE OF UNIT	PRICE PER MEASURE UNIT
*	Provide all line items with a unit price and a total cost. Leaving any item unaddressed may invalidate bid.	*****	*****	*****
*	>>>>>>>>Prices for the Period of 7-1-2016 - 6-30-2017<<<<<<<<	*****	*****	*****
292	Provide & Install Imitation slate install ceramic slate; 580 lbs. Per square; 60 year limited warranty. 10 7/8 inches X 16 inches with 90 lbs. Polyester reinforced felt underlayment. Install with stainless steel fasteners.	50	sq. ft.	$13.40
293	Provide & install reglets 5" max. s.o.	50	lf.	$5.25
294	Repair reglets	50	lf.	$5.25
295	Rake joints & cracks	100	lf.	$5.25
*	Restore pitch pockets	*****	*****	*****
296	a) Copper	1	ea.	$78.80
297	b) Aluminum	1	ea.	$78.80
*	Seal gutter joints	*****	*****	*****
298	a) Solder copper	50	lf.	$6.83
299	b) Liquid for aluminum	50	lf.	$78.80
300	Provide & install urethane sealant caulking	100	lf.	$5.25
	Provide & install Fascia metal trim. 6 inch width.			*****
301	a) Aluminum .032 gage	100	lf.	$3.68
302	b) Aluminum .040 gage	100	lf.	$4.73
303	c) Copper lead coated 16 oz.	100	lf.	$15.76
304	d) Copper uncoated 16 oz.	100	lf.	$13.13
*	Provide & install 5"x5" gutters and corrugated downspouts	*****	*****	*****
305	a) Copper uncoated	100	lf.	$57.78
306	b) Copper lead coated	100	lf.	$78.80
307	c) Aluminum seamless .032 gage	100	lf.	$10.51
308	d) Aluminum seamless .040 gage	100	lf.	$15.76
*	Provide & install counterflashing	*****	*****	*****
309	a) Copper uncoated	25	lf.	$10.51
310	b) Copper lead coated	50	sq. ft.	$15.76
311	c) Aluminum .032 gage	50	sq. ft.	$5.25
312	d) Aluminum .040 gage	25	sq. ft.	$6.30
*	Provide & install vent flashing	*****	*****	*****
313	a) Copper 16 oz.	20	sq. ft.	$2.62
314	b) Copper 20 oz.	20	sq. ft.	$3.15
315	c) Lead coated copper 16 oz.	20	sq. ft.	$3.68
316	d) Lead coated copper 20 oz.	20	sq. ft.	$4.20
*	Provide & install gravel stops and drip edges	*****	*****	*****
317	a) Copper uncoated 16 oz.	100	lf.	$15.76
318	b) Copper uncoated 20 oz.	100	lf.	$21.01
319	c) Copper lead coated 16 oz.	100	lf.	$26.27
320	d) Aluminum .032 gage	100	lf.	$10.51
321	e) Aluminum .040 gage	100	lf.	$12.61
322	Provide and install reglets 6" max S.O.	15	lf.	$10.51
323	Provide and install unreinforced peel and stick ice and water barrier	100	sq. ft.	$0.63
324	Provide all materials & labor necessary for test cuts to roof to ascertain the extent of damage.	1	cut	$236.39
325	Provide lab tests for asbestos for test cut of suspect roofing materials.	100	each test	$262.66
326	Provide hourly rates for estimators to do site visits and provide cost estimates for requested work.	50	Hours	$99.81
327	Journeyman roofer overtime rate per hour	100	Hours	$141.83
328	Carpenter overtime rate per hour	100	Hours	$105.06
*	Seal gutter joints	*****	*****	*****
329	a) solder copper	25	lf.	$52.53
330	b) liquid for aluminum	25	lf.	$15.76
*	Provide &Install Securock	*****	*****	*****
331	a) 3/8"	320	sq. ft.	$0.68
332	b) 1/2"	320	sq. ft.	$0.79
333	Provide 65' crane	1	per hour	$131.33
334	Provide 65' crane	1	per 1/2 day	$840.50
335	Provide 65' crane	1	per day	$1,575.94
336	Provide and install styrene based liquid applied roofing. (similar to Kemper).	500	sq. ft.	$7.35
*	Provide and install CHEM CURB liquid applied Pitch pockets	*****	*****	*****
337	a) 4 1/2" I.D.	1	ea	$577.84
338	b) 7 1/2" I.D'	1	ea	$682.91
339	Discount off list for materials not listed.	Percent	%	

ATTACHMENT "A" - SOLICITATION PRICING SHEET

LINE	Solicitation #7549007	ESTIMATED QUANTITY	MEASURE OF UNIT	PRICE PER MEASURE UNIT
*	Provide all line items with a unit price and a total cost. Leaving any item unaddressed may invalidate bid.	*****	*****	*****
*	>>>>>>>>Prices for the Period of 7-1-2017 - 12-31-2017<<<<<<<<	*****	*****	*****
*	Remove existing, provide & install new EPDM (rubber) membrane	*****	*****	*****
340	a) Fully Adhered	500	sq. ft.	$6.46
341	b) Ballasted	500	sq. ft.	$7.00
342	c) Mechanically Fastened	500	sq. ft.	$6.46
*	Repair seams or replace damaged EPDM including all necessary prep work.	*****	*****	*****
343	a) Fully Adhered	250	lf.	$10.77
344	b) Ballasted	250	lf.	$16.15
345	c) Mechanically Fastened	250	lf.	$10.77
*	Prepare existing surface and provide & install Modified Bitumen membrane.	*****	*****	*****
346	a) 4mm APP to smooth surface	500	sq. ft.	$4.31
347	b) 4mm APP to gravel surface	500	sq. ft.	$5.38
348	c) 4mm SBS to smooth surface	500	sq. ft.	$5.38
349	d) 4mm SBS to gravel surface	500	sq. ft.	$7.00
*	Remove existing, provide & install single ply membrane of:	*****	*****	
350	a) PVC	500	sq. ft.	$6.46
351	b) CPE	500	sq. ft.	$6.46
352	c) Tripolimer	500	sq. ft.	$6.46
353	Remove existing, provide & install built up 4 ply fiberglass type IV roofing felts in hot Perma mop roofing asphalt	500	sq. ft.	$12.92
354	Provide & install 5 courses of plastic cement and webbing overlayment.	10	sq. ft.	$10.77
*	Provide & install overlayment of 60 lbs. floodcoat of Perma Mop roofing asphalt with 400 lbs. gravel 3/8, 5/8 inch size at a uniform rate. (per 100 sq. ft.)	*****	*****	*****
355	a) Smooth surface	500	sq. ft.	$13.46
356	b) Graveled surface	1,000	sq. ft.	$16.15
357	Patch joints in corrugated metal roofing.	100	lf.	$10.77
358	Blister repair (area encompassing blister) 1-ft. extension cuts.	50	sq. ft.	$3.23
359	Provide & install asphalt emulsion non-fiberated roof coating.	250	sq. ft.	$3.77
360	Provide & install aluminum non-fiberated roof coating.	1	gal.	$2.15
361	Remove existing rolled roofing, provide & install mineral- surfaced rolled roofing over exposed roof deck.	100	sq. ft.	$2.69
362	Provide & install uncured EPDM 12" wide strip for seam resealent	100	lf.	$16.15
363	Provide & install, peel & stick nominal 25 mil cured butyl tape	100	lf.	$10.77
364	Provide & install non-fiberated flashing cement.	1	gal.	$26.92
365	Provide & install tar roof re-saturant	1	gal.	$26.92
366	Provide & install a #28 fiberglass base sheet in a full mopping of hot Perma Mop roofing asphalt as a vapor barrier	500	sq. ft.	$10.77
*	Provide & install polyisocyanurate asphalt faced roofing insulation	*****	*****	*****
367	a) 1 inch thickness	500	sq. ft.	$1.62
368	b) 2 inch thickness	500	sq. ft.	$2.15
369	c) 3 inch thickness	500	sq. ft.	$2.69
*	Provide & install tapered polyisocyanurate asphalt faced	*****	*****	*****
370	a) 1/8" per ft.taper	500	sq. ft.	$3.23
371	b) 1/4" per ft.taper	500	sq. ft.	$4.31
372	Provide & install Tapered fiberboard 1/8" per ft. taper	500	sq. ft.	$3.77
373	Provide & install 1/2 inch fiberboard (High Density)	500	sq. ft.	$4.85
*	Remove existing, provide & install Wood nailers (pressure treated)	*****	*****	*****
374	a) 2"x 6"	100	bf.	$5.38
375	b) 2"x 8"	100	bf.	$6.46
*	Remove existing, provide & install plywood sheathing	*****	*****	*****
376	a) 1/2"	32	sq. ft.	$0.65
377	b) 3/4"	32	sq. ft.	$0.81
378	c) 1"	32	sq. ft.	$1.08
*	Remove existing, provide & install t&g	*****	*****	*****
379	a) 1"x 4"	100	bf.	$1.08
380	b) 1"x 6"	100	bf.	$1.29
381	c) 1"x 8"	100	bf.	$1.62
382	d) 2"x 4"	50	bf.	$5.38
383	e) 2"x 6"	50	bf.	$6.46
*	Remove existing, provide & install trim & fascia board.	*****	*****	*****
384	a) 1"x 4"	25	bf.	$1.08
385	b) 1"x 6"	50	bf.	$1.35
386	c) 1"x 8"	50	bf.	$1.62
387	d) 2"x 6"	25	bf.	$2.15
388	e) 2"x 8"	25	bf.	$5.38
389	Provide & install 4" x 4" lumber (pressure treated)	50	bf.	$6.46
*	Repair or replace rafter tails (pressure treated)	*****	*****	*****
390	a) 2" x 4"	50	bf.	$5.38
391	b) 2" x 6"	50	bf.	$6.46
392	c) 2" x 8"	50	bf.	$8.62
*	Remove existing shingles and replace over exposed roof deck 15 lb. felt with 40 year limited warranty Fiberglass asphalt shingles.	*****	*****	*****
393	a) (3 tab) (ASTM-ANSI D-312) minimum weight 320 lbs. per sq.	1,000	sq. ft.	$3.77
*	Provide & install 30 year limited warranty Fiberglas asphalt shingles over existing roof covering.	*****	*****	*****
394	a) (3 Tab) (ASTM-ANSI D-312) Minimum weight 265 lbs. per sq.	1,000	sq. ft.	$3.77
395	Provide & install ridge vents 18 sq. inches free air per lineal ft.	50	lf.	$3.55
	Provide & install soffit vents 9 sq. inches free air per lineal ft.			*****
396	a) one story building	50	lf.	$5.38
397	b) two story building	50	lf.	$7.54
398	c) three story building	50	lf.	$10.77
399	d) four story building	50	lf.	$16.69

ATTACHMENT "A" - SOLICITATION PRICING SHEET

LINE	Solicitation #7549007	ESTIMATED QUANTITY	MEASURE OF UNIT	PRICE PER MEASURE UNIT
*	Provide all line items with a unit price and a total cost. Leaving any item unaddressed may invalidate bid.	*****	*****	*****
*	>>>>>>>>Prices for the Period of 7-1-2017 - 12-31-2017<<<<<<<<	*****	*****	*****
*	Provide & Install replacement roofing slates with 90 lbs. Polyester reinforced felt underlayment to match existing in color, thickness, texture, size. install with copper nails.	*****	*****	*****
400	a) 4 inch width	50	lf.	$37.69
401	b) 6 inch width	50	lf.	$48.46
402	c) 8 inch width	50	lf.	$59.23
403	d) 10 inch width	50	lf.	$70.00
404	e) 12 inch width	50	lf.	$70.00
405	Provide & Install Imitation slate install ceramic slate; 580 lbs. Per square; 60 year limited warranty. 10 7/8 inches X 16 inches with 90 lbs. Polyester reinforced felt underlayment. Install with stainless steel fasteners.	50	sq. ft.	$13.73
406	Provide & install reglets 5" max. s.o.	50	lf.	$5.38
407	Repair reglets	50	lf.	$5.38
408	Rake joints & cracks	100	lf.	$5.38
*	Restore pitch pockets	*****	*****	*****
409	a) Copper	1	ea.	$80.77
410	b) Aluminum	1	ea.	$80.77
*	Seal gutter joints	*****	*****	*****
411	a) Solder copper	50	lf.	$7.00
412	b) Liquid for aluminum	50	lf.	$80.77
413	Provide & install urethane sealant caulking	100	lf.	$5.38
*	Provide & install Fascia metal trim. 6 inch width.	*****	*****	*****
414	a) Aluminum .032 gage	100	lf.	$3.77
415	b) Aluminum .040 gage	100	lf.	$4.85
416	c) Copper lead coated 16 oz.	100	lf.	$16.15
417	d) Copper uncoated 16 oz.	100	lf.	$13.46
*	Provide & install 5"x5" gutters and corrugated downspouts	*****	*****	*****
418	a) Copper uncoated	100	lf.	$59.23
419	b) Copper lead coated	100	lf.	$80.77
420	c) Aluminum seamless .032 gage	100	lf.	$10.77
421	d) Aluminum seamless .040 gage	100	lf.	$16.15
*	Provide & install counterflashing	*****	*****	*****
422	a) Copper uncoated	25	lf.	$10.77
423	b) Copper lead coated	50	sq. ft.	$16.15
424	c) Aluminum .032 gage	50	sq. ft.	$5.38
425	d) Aluminum .040 gage	25	sq. ft.	$6.46
*	Provide & install vent flashing	*****	*****	*****
426	a) Copper 16 oz.	20	sq. ft.	$2.69
427	b) Copper 20 oz.	20	sq. ft.	$3.23
428	c) Lead coated copper 16 oz.	20	sq. ft.	$3.77
429	d) Lead coated copper 20 oz.	20	sq. ft.	$4.31
*	Provide & install gravel stops and drip edges	*****	*****	*****
430	a) Copper uncoated 16 oz.	100	lf.	$16.15
431	b) Copper uncoated 20 oz.	100	lf.	$21.54
432	c) Copper lead coated 16 oz.	100	lf.	$26.92
433	d) Aluminum .032 gage	100	lf.	$10.77
434	e) Aluminum .040 gage	100	lf.	$12.92
435	Provide and install reglets 6" max S.O.	15	lf.	$10.77
436	Provide and install unreinforced peel and stick ice and water barrier	100	sq. ft.	$0.65
437	Provide all materials & labor necessary for test cuts to roof to ascertain the extent of damage.	1	cut	$242.30
438	Provide lab tests for asbestos for test cut of suspect roofing materials.	100	each test	$269.22
439	Provide hourly rates for estimators to do site visits and provide cost estimates for requested work.	50	Hours	$102.30
440	Journeyman roofer overtime rate per hour	100	Hours	$145.38
441	Carpenter overtime rate per hour	100	Hours	$107.69
*	Seal gutter joints	*****	*****	*****
442	a) solder copper	25	lf.	$53.84
443	b) liquid for aluminum	25	lf.	$16.15
	Provide &Install Securock			*****
444	a) 3/8"	320	sq. ft.	$0.70
445	b) 1/2"	320	sq. ft.	$0.81
446	Provide 65' crane	1	per hour	$134.61
447	Provide 65' crane	1	per 1/2 day	$861.51
448	Provide 65' crane	1	per day	$1,615.34
449	Provide and install styrene based liquid applied roofing. (similar to Kemper).	500	sq. ft.	$7.54
*	Provide and install CHEM CURB liquid applied Pitch pockets	*****	*****	*****
450	a) 4 1/2" I.D.	1	ea	$592.29
451	b) 7 1/2" I.D'	1	ea	$699.98
452	Discount off list for materials not listed.	Percent	%	

Form W-9 (Rev. 3/7/11)

State of Rhode Island
PAYER'S REQUEST FOR TAXPAYER IDENTIFICATION NUMBER AND CERTIFICATION

THE IRS REQUIRES THAT YOU FURNISH YOUR TAXPAYER IDENTIFICATION NUMBER TO US. FAILURE TO PROVIDE THIS INFORMATION CAN RESULT IN A $50 PENALTY BY THE IRS. IF YOU ARE AN INDIVIDUAL, PLEASE PROVIDE US WITH YOUR SOCIAL SECURITY NUMBER (SSN) IN THE SPACE INDICATED BELOW. IF YOU ARE A COMPANY OR A CORPORATION, PLEASE PROVIDE US WITH YOUR EMPLOYER IDENTIFICATION NUMBER (EIN) WHERE INDICATED.

Taxpayer Identification Number (T.I.N.)

Enter your taxpayer identification number in the appropriate box. For most individuals, this is your social security number.

Social Security No. (SSN) [ ] [ ] [ ]

Employer ID No. (EIN) 06 0971347

NAME Pawcatuck Roofing Co., Inc.

ADDRESS 20 S. Anguilla Rd., Box 9B, Pa.

(REMITTANCE ADDRESS, IF DIFFERENT)

CITY, STATE AND ZIP CODE Pawcatuck CT 06379

CERTIFICATION: Under penalties of perjury, I certify that:

(1) The number shown on this form is my correct Taxpayer Identification Number (or I am waiting for a number to be issued to me), and
(2) I am not subject to backup withholding because either: (A) I have not been notified by the Internal Revenue Service (IRS) that I am subject to backup withholding as a result of a failure to report all interest or dividends, or (B) the IRS has notified me that I am no longer subject to backup withholding.

Certification Instructions -- You must cross out item (2) above if you have been notified by the IRS that you are subject to backup withholding because of under-reporting interest or dividends on your tax return. However, if after being notified by IRS that you were subject to backup withholding you received another notification from IRS that you are no longer subject to backup withholding, do not cross out item (2).

PLEASE SIGN HERE

SIGNATURE [signature] **TITLE** President **DATE** 10/15/14 **TEL NO.** 860 599 1024

BUSINESS DESIGNATION:

Please Check One: Individual ☐ Medical Services Corporation ☐ Government/Nonprofit Corporation ☐
Partnership ☐ Corporation ☑ Trust/Estate ☐ Legal Services Corporation ☐

NAME: Be sure to enter your full and correct name as listed in the IRS file for you or your business.

ADDRESS, CITY, STATE AND ZIP CODE: Enter your primary business address and remittance address if different from your primary address). If you operate a business at more than one location, adhere to the following:

1) Same T.I.N. with more than one location -- attach a list of location addresses with remittance address for each location and indicate to which location the year-end tax information return should be mailed.
2) Different T.I.N. for each different location -- submit a completed W-9 form for each T.I.N. and location. (One year-end tax information return will be reported for each T.I.N. and remittance address.)

CERTIFICATION -- Sign the certification, enter your title, date, and your telephone number (including area code and extension).

BUSINESS TYPE CHECK-OFF -- Check the appropriate box for the type of business ownership.

Mail to: Supplier Coordinator, One Capitol Hill, Providence, RI 02908

STATE OF RHODE ISLAND

CONTRACTORS' REGISTRATION
AND LICENSING BOARD

COMMERCIAL ROOFER

REGISTRATION NO. 43R

EXP. DATE 03/1/16

REGISTRANT'S NAME
PAWCATUCK ROOFING CO., INC.

AUTHORIZED REPRESENTATIVE
ROBERT J HOLLAND

DRIVER'S LICENSE #
CT 074641682

EXECUTIVE DIRECTOR